

Community Background Located in a mountainous region Ngöbe People 300-400 People in Community Subsistence Farming Learn Spanish in School Ngöbe girls in traditional dresses Photo by Brittany Allen

Project Objectives and Background

- Primary Objective
 - Design a sustainable way to provide the community with clean water
- Existing Systems
 - Old System
 - New System
- Project Objectives
 - Improve Existing System
 - Expand System
 - Educate People on
 Use and Maintenance




Storage tank for the new system in Cerro Miel Photo by Merete Sørum





Data Collection


- Survey and GPS
- Water Quality
- Water Availability

Team members doing water quality testing Photo by Manda Schierbeek









Water Availability and Quality



- Old system
 - Flow rate: 4.8 gal/min
 - Spring source
 - Good quality
- New system:
 - Flow rate: 50.7 gal/min
 - River source
 - Low quality

Stream in Cerro Miel





Photo by Elizabeth Jefferson


Water Treatment


- Slow Sand Filter
- Inline Chlorination
- Located in Tugri
- Suggested move to Cerro Miel

Slow sand filter in Tugri









Pressure Release

- High elevation changes cause high pressures in pipes
- Two options considered
 - Mason-Break Pressure Tanks
 - HDP Pressure Tanks





Mason-Break Pressure Tanks





Barefooteconomics.com


- 3 Tanks Total
- Located within Cerro Miel
- Most Durable Option

















Water Hammer

- Pressure increases from rapidly closing valve
- Additional pressure may cause pipe to break









Cost Estimating

- Material Data
 - Bajo Salitre Cost Estimate
 - Online Quotes
- Key Assumptions:
 - No Labor Cost
 - No Equipment Cost





Coinquest.con

Final Cost Estimate

<u>ltem</u>	<u>Cost</u>
Pipeline, Fittings, Valves	4350
Pressure Release	535
Air Release	215
Gully Crossing Supports	1380
UV Protection	440
Transportation of Materials	930
Total:	\$7,850

Construction Schedule

- Total time to construct: 105 Days
- Key Assumptions
 - Crew of 17 workers each day
 - 0.5 mi of pipe can be laid per day
 - RS Means Data Valid



Ngöbe women in traditional dresses Photo by Elizabeth Jefferson

Conclusions

- Met the community's needs
- Designed a sustainable, reliable, and economical project
- Supplied tools to help community maintain their system



Photo by Mike Drewyor





